



Bharat Sanchar Nigam Ltd.

(A GOVT OF INDIA ENTERPRISES)

O/O Sub Divisional Engineer , BSNL ESD Room No 4, BSNL Bhawan, Bhota Chowk
Hamirpur(HP)

NO:- SDE/E/BSNL/ESD/HMR/80

Date:-22.11.2018

Notice Inviting Quotation

The Sub-Divisional Engineer (E) B.S.N.L., Electrical Sub-Division, **Room no 4, Ground floor BSNL Bhawan Bhota chowk , Hamirpur-177001** invites on behalf of Bharat Sanchar Nigam Limited sealed quotations for the work mentioned below. The quotation must reached on 28.11.2018 up to 15.00Hrs at this office & will be opened on the same day at 15.30Hrs . The nature of the job and quantum of work has been explained in the schedule given below. The quotations can be downloaded from www.hp.bsnl.co.:-

Name of work:- Repairing electrical wiring and distribution box at TE building bhoranj (HMR)						
S. No.	Description of items	Qty		Rate	Unit	Amount
1	S/Replacement of (6-32)amp faulty mcb in the existing MCB DB complete with connection as reqd	7	Nos		each	
2	Replacement existing 2x1.5sqmm pvc copper conductor FR wire in existing conduit i/c testing etc as reqd	20	Mtr		Mtr	
3	Replacement existing 2x4sqmm pvc copper conductor cable in existing conduit i/c testing etc as reqd	15	mtr		mtr	
4	Replacement existing 4x4sqmm pvc copper conductor cable in existing conduit i/c testing etc as reqd	10	mtr		mtr	
5	SITC of 20W prewired surface / recess mounted (minimum colour code 840) LED light fixture & integrated electronic driver including connection with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable and earthing etc. as required. (Preferred makes SYSKA/ Philips/ Wipro/ Havells/ Crompton/ Bajaj/ Osram)	5	Nos		each	
6	Supplying and fixing of 25MM of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed cutting the wall and making good the same in case of recessed	21	mtr		mtr	
7	S/Replacement of existing 15 amp 6pin soocket and 15 amp piano type switch complete with tesing etc as reqd	1	Nos		each	
				Total		

(Contractor sign with seal)

- 1 The work shall be carried out as per CPWD specification /sheet attached.

- 2 The work shall be carried out as per instruction of Engineer-in charge.
The rates shall be inclusive of all type taxes i.e. Exise duty, Sales tax, CST, octroi,
- 3 Work contact tax and **Excluding GST**.
- 4 The quoted rates shall be all inclusive of cartage, handling and all labour charges. Nothing extra shall be paid on this account.
Suitable deduction as rates specified by the state authorities for work contract tax and Income Tax shall be deducted from the contractor bills.
- 5
- 6 The makes and model used as per sheet attached.
- 7 F.O.R. destination rates should be quoted.
- 8 Time allowed for completion of job is 7Days

----S/D----
Sub Divisional Engineer(E)
BSNL Electrical Sub Div
Hamirpur

NIO:-

Copy to :- All enlisted contractors& BSNL HP web site www.hp.bsnl.co.in
EE(E) BSNL ED dharamshala for information pl