



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Sub Divisional Engineer (E), B.S.N.L. Electrical Sub Division

**Head Post office complex BSNL CSC building Dharamshala 176215 . Tele No. 01892-222500, 9418038384
FAX 01892 222501**

No. SDE/E/BSNL/ESD/DMA/2018-2019/13

Dated: 03-10-2018

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/s G.S. Electrical Works Vill & P.O. Amb, Distt., Una (HP).
3. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
4. M/s. Perfect Engineers , 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
5. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
6. M/S Ravindra Enterprises opposite petrol pump main Bazaar Ner Chowk Mandi (HP)
7. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
8. M/s Parlax Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi
9. M/s Dharmendar singh Ghutkar Mandi

Sub: - NIQ for the work: - : - Replacement of Faulty Three Phase Power cable at BTS site Fatepur under SSA Dharamshala (HP)

NOTICE INVITING QUOTATION

The sub Division al Engineer (E) BSNL Electrical sub Division Dharamshala invite on behalf of Bharat Sanchar Nigam Limited Sealed quotations for the work mentioned above & as per schedule of work (attached as annexure-A) . The Sealed quotation will be received up 3.00 P.M on dated 08-10-2018 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Terms & conditions:-

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 3 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

Sub-Divisional Engineer (E)

Name of work :- Replacement of Faulty Three Phase Power cable at BTS site Fatepur under SSA Dharamshala (HP)

Sr.No.	Description of item.	Quantity		Rate	Unit	Amount
1	Supplying & Laying 3.5x25 sqmm size one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade on the ground / wall /Surface / existing cable tray complete as required.	15	Mtrs		Mtr	
2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.					
	a) 3.5 x25 sqmm	2	Set		Set	

Total Rs. =

Sub-Divisional Engineer (E)
B.S.N.L. Elect. Sub-Division,
Dharamshala