



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Sub Divisional Engineer (E), B.S.N.L. Electrical Sub Division

**Head Post office complex BSNL CSC building Dharamshala 176215 . Tele No. 01892-222500, 9418038384
FAX 01892 222501**

No. SDE/E/BSNL/ESD/DMA/2017-2018/

Dated: 22-11-2017

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/S Hydraulic Engineering Co. hospital Road Solan (HP).
3. M/s Om Earth Movers, Sundernagar.
4. M/s G.S. Electrical Works Vill & P.O. Amb, Distt,. Una (HP).
5. M/s Marco, Air conditioning & refrigeration Engineers, 52 CR block Dilshad garden Delhi-95
6. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
7. M/s. Perfect Engineers , 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
8. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
9. M/s Gopal Krishan Contractor,.1310, sector -50B, progressive Society , Chandigarh.
10. M/S Ravindra Enterprises opposite petrol pump main Bazar Ner Chowk Mandi (HP)
11. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
12. M/s Parlax Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi

Sub: - NIQ for the work :- Replacement of Change Over Switch and other Associated work at TE building at Khera (HP) under SSA Dharamshala (HP).

Sub-Divisional Engineer (E)

NOTICE INVITING QUOTATION

The sub Division al Engineer (E) BSNL Electrical sub Division Dharamshala invite on behalf of Bharat Sanchar Nigam Limited Sealed quotations for the work mentioned above & as per schedule of work (attached as annexure-A) . The Sealed quotation will be received up 3.00 P.M on dated 25-11-2017 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Terms & conditions:-

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 3 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

Sub-Divisional Engineer (E)

Schedule of work

Name of work: - Replacement of Change Over Switch and other Associated work at TE building at Khera (HP) under SSA Dharamshala (HP).						
Sr.No.	Description of item.	Quantity		Rate	Unit	Amount
1	Dismantling The existing Cable laid for for Change over switch in existing Panel i/c making the route of cable suitable for installing the new Change over in side the room complete as required at site.	1	Job		Job	
2	Replacement of faulty / burnt 125 Amps on Load change over Switch with 63 A front handle operated Sheet Steel enclosed on wall i/c making inter connection after dismantling the existing faulty switch complete as required at site.	1	No.		Each	
3	Supplying & Laying 4x16 sqmm size one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade on the wall /Surface / existing cable tray complete as required.	12	Mtrs		Mtr	

TOTAL Rs. _____

Sub-Divisional Engineer (E)
B.S.N.L. Elect. Sub-Division,
Dharamshala