



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Sub Divisional Engineer (E), B.S.N.L. Electrical Sub Division

Head Post office complex BSNL CSC building Dharamshala 176215 . Tele No. 01892-222500, 9418038384 FAX 01892 222501

No. SDE/E/BSNL/ESD/DMA/2017-2018/

Dated:- 23-08-2017

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/S Hydraulic Engineering Co. hospital Road Solan (HP).
3. M/s Om Earth Movers, Sundernagar.
4. M/s G.S. Electrical Works Vill. & P.O. Amb, Distt, Una (HP).
5. M/s Marco, Air conditioning & refrigeration Engineers, 52 CR block Dilshad garden Delhi-95
6. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
7. M/s. Perfect Engineers , 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
8. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
9. M/s Gopal Krishan Contractor, .1310, sector -50B, progressive Society , Chandigarh.
10. M/S Ravindera Enterprises opposite petrol pump main Bazar Ner Chowk Mandi (HP)
11. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
12. M/s Parlax Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi

Sub: - NIQ for the work :- **Shifting & reinstallation of LT Panel & other associated accessories at TE Daulatpur (HP)**

SPECIFICATIONS.

1. Work shall be carried out as per BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 2 days from the date of issue of this work order.
5. The firm shall quote rates for all items inclusive of all duties , octroi & levies, packing, Forwarding, freight and insurance etc. as mentioned **except GST** applicable to works contract.

Sub-Divisional Engineer (E)

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned as per sheet attached / given below: -Sealed quotation with your item rate should reach to the undersigned at 3.00 P.M on 26-08-2017 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Sub-Divisional Engineer (E)

Name of work :-Shifting & reinstallation of L.T. Panel & other associated accessories at TE Daulatpur (HP)						
Sr.No	Description Of Items	Qty		Rate	Unit	Amount
1	Dismantling of Distribution Panel, i/c disconnecting the power supply & electrical accessories / Associated work like cables, cable tray complete as required at site	1	Job		Job	
2	shifting & Reinstallation of distribution panel & other associated accessories in the other room in the existing TE at suitable place i/c making the connection by laying all the outgoing & incoming cables on the wall ceiling / existing cable tray complete as required.	1	Job		Job	
3	Laying & fixing XLPE Aluminium conductor armoured cable of 1.1 KV grade of following sizes in the surface of wall / existing cable tray etc. as required					
	a) 3.5 x 25sqmm	25	Mtrs.		Mtr.	

Total Rs. = _____

Sub-Divisional Engineer (E)
B.S.N.L. Elect. Sub-Division,
Dharamshala

SPECIFICATIONS.

1. Work shall be carried out as per BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 2 days from the date of issue of this work order.
5. The firm shall quote rates for all items inclusive of all duties, octroi & levies, packing, Forwarding, freight and insurance etc. as mentioned **except GST** applicable to works contract law.

Sub-Divisional Engineer (E)