

**BHARAT SANCHAR NIGAM LIMITED****भारत संचार निगम लिमिटेड**(A Govt. of India Enterprise )  
(भारत सरकार का उपक्रम)**O/o Sub Divisional Engineer (E),BSNL Electrical Sub Division, 1<sup>st</sup> Floor Block No. 35 Kasumpati Shimla-171009**

कार्यालय उप मंडल अभियंता ( विद्युत ) भारत संचार निगम लिमिटेड ब्लॉक न. ३५ शिमला

No:-314SDE/E/BSNL/ESD./SML/18-19/ 231

Dated:- 12.03.2019

**Notice Inviting Quotation**

The Sub Divisional Engineer (Elect) BSNL, Electrical Sub Division, 1<sup>st</sup> Floor Block No.35 Kasumpati Shimla-171009 invites the sealed Spot quotation for the work name mentioned below. The quotations must reached on **15.03.2019** up 15.00 Hrs.at this office & will be opened on the same day at 15.30 Hrs. The nature of job and quantum of work has been explained in the schedule given below.

**NAME OF WORK: - Replacement of GO Switch & Lightening arrestor of 2x400 KVA Sub Station at CTO Shimla**

S. No.	Description of items	Qty	Rate	Unit	Amount
	Replacement of 11 KV gang operated switch for controlling incoming supply having 3 Nos,11KV post type insulator per phase,copper or copper alloyed high pressure heavily tinned contacts and required MS arching horns capable of breaking magnetizing current complete with horizontal connecting bar i/c connections etc as reqd. ( Old dismantalled items will be contractor property)	2 Set		Set	
	Supplying and erection of three piece non linear register type lightening arrestor suitable for 3 wire, 11KV over head lines with rated voltage of 9KV (rms) with nominal discharge current rating of 5KA and complete with galvanized clamping arrangement G.I. bolts, nuts, washers etc. as required. ( Old dismantalled items will be contractor property)	2 Set		Set	
<b>Total</b>					

Note:-

- 1 The work shall be done as per the specification of department.
2. The work shall be supervised by the qualified Engineer-in-charge or his duly authorized representative at the site of work.
3. The layout of the work will be given by the Engineer-in-charge or his duly authorized representative at the site of work.
4. Any damage done to the building by the contractor during the execution of work shall be made good by the contractor at his risk and cost, if the damage are not made good by the contractor in reasonable time determine by the Engineer-in-charge the same will be got done at his cost departmentally after serving notice to him.
5. No extra payment will be made for any kind of transportation.
- 6 **The rates quoted should be inclusive of all taxes & duties but excluding GST which will be paid extra**
7. Time allowed for completion of work shall be **10 Days**

--Sd----

Sub Divisional Engineer (Elect)  
BSNL Electrical Division  
Shimla

From

M/s.....

Contractor Signature with Seal

NIO:

Copy to :- All Enlisted Contractor & BSNL HP Web Site [www.hp.bsnl.co.in](http://www.hp.bsnl.co.in)  
EE(E),BSNL,EZ,Shimla for information please