



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Executive Engineer (Elect.), B.S.N.L Electrical Division ,Head Post Office ,
Complex, BSNL CSC Building Dharamshala, district Kangra (HP)
Tel :- 01892-223301

NO:- EE/E/BSNL/ED/DMA /2019-2020/103

Dated 11-07-2019

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/s G.S. Electrical Works Vill & P.O. Amb, Distt., Una (HP).
1. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
2. M/s. Perfect Engineers, 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
3. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
4. M/S Ravindra Enterprises opposite petrol pump main Bazaar Ner Chowk Mandi (HP)
5. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
6. M/s Parlux Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi
7. M/s Dharmendar singh Ghutkar Mandi.
8. M/s Rajindra Engineering works railway Gurudawara complex Gurdaspur Road Pathankot.

Sub: -NIQ for the work:- Replacement of faulty Change Over Switch MCBDB & other Associated work at Telephone Exchange Bhatoli under SSA Dharamshala district Kangra HP).

NOTICE INVITING QUOTATION

The Executive Engineer (E) BSNL Electrical Division Dharamshala invite on behalf of Bharat Sanchar Nigam Limited Sealed quotations for the work mentioned above & as per schedule of work (attached as annexure-A) . The Sealed quotation will be received up 3.00 P.M on dated 17-07-2019 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Terms & conditions:-

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 5 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

**Executive Engineer(E)
BSNL Electrical Division
Dharamshala (HP)**

Schedule of quantity

Name of work :- Replacement of faulty Change Over Switch MCBDB & other Associated work at Telephone Exchange Bhatoli under SSA Dharamshala district Kangra HP).						
S. N.	Description of item.	Quantity		Rate	Unit	Amount
1	Dismantling The existing faulty / burnt change over panel, MCBDB, MCBs and disconnection of cables for incoming & outgoing connection complete as required at site .	1	Job		Job	
2	Providing and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs) and with 4 pole 63 Amps 35 KA MCCB as incomer interconnection as required . (Crompton Havells / Indokopp / MDS Legrand / L&T)					
	8 way (4 + 24), Double door.	1	No.		Each	
3	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. (Crompton Havells / Indokopp / MDS Legrand / L&T)					
	a) Single pole	2	Nos.		Each	
	b) Double pole	2	Nos.		Each	
	c) Triple pole	4	Nos.		Each	
4	Replacement of faulty / burnt Change over switch with 63 Amps on load change over switch in sheet enclosure, 415 volt 50Hz AC supply i/c interconnection complete as required at site.(HPL / Havells / H-H Elcon)	1	No.		Each	
5	Supplying and fixing 63 A 415 Volt rewirable Kit Kat (Porcelain Fuse carrier & base) i/c making connections complete as required at site.	3	Nos.		Each	
TOTAL Rs.						

SPECIFICATIONS.

1. Work shall be carried out as per BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost. Time allowed to carry out the work is 5 days from the date of issue of this work order.
4. The rate should be quoted inclusive of all taxes i/c GST

CONTRACTOR

Executive Engineer (E)
BSNL Electrical Division
Dharamshala (HP)