



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

*O/o Executive Engineer (Elect.), B.S.N.L Electrical Division ,Head Post Office ,
Complex, BSNL CSC Building Dharamshala, district Kangra (HP)
Tel :- 01892-222501*

NO:- 21(07)EE/E/BSNL/ED/DMA /2019-2020/131

Dated 31-07-2019

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/s G.S. Electrical Works Vill & P.O. Amb, Distt., Una (HP).
1. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
2. M/s. Perfect Engineers, 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
3. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
4. M/S Ravindra Enterprises opposite petrol pump main Bazaar Ner Chowk Mandi (HP)
5. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
6. M/s Parlux Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi
7. M/s Dharmendar singh Ghutkar Mandi.
8. M/s Rajindra Engineering works railway Gurudawara complex Gurdaspur Road Pathankot.

Sub: -NIQ for the work:- Replacement /repair of tube lights & additional fitting at CSC Dharamshala (HP).

NOTICE INVITING QUOTATION

The Executive Engineer (E) BSNL Electrical Division Dharamshala invite on behalf of Bharat Sanchar Nigam Limited Sealed quotations for the work mentioned above & as per schedule of work (attached as annexure-A) . The Sealed quotation will be received up 3.00 P.M on dated 08/08/2019 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Terms & conditions:-

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 5 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

**Executive Engineer(E)
BSNL Electrical Division
Dharamshala (HP)**

Schedule of quantity

Name of work :- Replacement /repair of tube lights & additional fitting at CSC Dharamshala (HP).						
Sr. No.	Description of item.	Quantity		Rate	Unit	Amount
1	SITC of decorative ultra slim round profile LED lighting fixture with extruded polycarbonate environmental friendly, energy efficient ready to use with all accessories suitable for operation on 230 volt 50 Hz AC supply directly on ceiling wall i/c making connections with 1.5 sqmm. FR PVC insulated cooper conductor single core cable etc as required at site (m/s Havells LHXBPL7PN1W020 or S.S. make.)	2	Nos.		Each	
2	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
	a) 4 way SPN Double door.	1	No.		Each	
3	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	a) Single pole	2	Nos.		Each	
	b) Double pole	1	Nos.		Each	
4	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
	a) 25 mm	11	Mtrs.		Mtr.	
5	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required					
	a) 6x4 sqmm	16	Mtrs		Mtr.	
6	Replacement of faulty / burnt choke of existing fitting with Electronic blast suitable for 36W/40 W FTL fitting i/c making connection complete as required (make Havells Model LHGEAFBBDPA1036 or Equivalent S.S. Make)	10	Nos.		Each	
7	Replacement of following faulty accessories i/c making connection testing complete as required.					
	a) 36 watt T8FTL 6500 K Fluorescent Tubular lamp	10	Nos.		Each	
				TOTAL Rs.		

SPECIFICATIONS.

1. Work shall be carried out as per BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 5 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

**Executive Engineer (E)
BSNL Electrical Division
Dharamshala (HP)**