



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Executive Engineer (Elect.), B.S.N.L Electrical Division ,Head Post Office ,
Complex, BSNL CSC Building Dharamshala, district Kangra (HP)
Tel :- 01892-222501

NO:- EE/E/BSNL/ED/DMA /2019-2020/241

Dated 04-01-2020

To

1. M/s R.R. Electrical Co. V& P.O Kotkawala Teh. Distt Kangra (HP).
2. M/s G.S. Electrical Works Vill & P.O. Amb, Distt., Una (HP).
1. M/S Geol. Electric works , 80 P Road Ferojpur (Pb).
2. M/s. Perfect Engineers, 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
3. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
4. M/S Ravindra Enterprises opposite petrol pump main Bazaar Ner Chowk Mandi (HP)
5. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
6. M/s Parlux Electrical Engineers & Traders Near Bus Stand Joginder Nagar Distt Mandi
7. M/s Dharmendar singh Ghutkar Mandi.
8. M/s UK Engineers Lower bazaar , Kashmiri Masjid Shimla (HP)

Sub: -NIQ for the work:- SITC of 3X7 TR Precision type package AC units for OCB Exchange at TE Building Dharamshala (HP) (SH:- Provision of Console panel & other associated work)

NOTICE INVITING QUOTATION

The Executive Engineer (E) BSNL Electrical Division Dharamshala invite on behalf of Bharat Sanchar Nigam Limited Sealed quotations for the work mentioned above & as per schedule of work (attached as annexure-A) . The Sealed quotation will be received up 3.00 P.M on dated 09-01-2020 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day.

Terms & conditions:-

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 7 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

**Executive Engineer(E)
BSNL Electrical Division
Dharamshala (HP)**

Annexure-A

SCHEDULE OF QUANTITY

Name of Work :-SITC of 3X7 TR Precision type package AC units for OCB Exchange at TE Building Dharamshala (HP) (SH:- Provision of Console panel & other associated work)						
S.No.	Description of Items	Qty.		Rate	Unit	Amount
1	Providing and fixing of audio visual consol panel fabricated out of 16SWG MS sheet and powder coated including Providing & Fixing control contactors of L&T make necessary wiring, push button, indication, hooter etc for following controls as required.					
	a) Switch Room Temperature higher than preset value.					
	B) Fire alarm & Tripping System (for 3 nos. Pkg units)					
	c) Fresh air fan failure.	1	Job		Job	
2	Supplying and fixing of PVC insulated PVC sheathed/XLPE Copper Conductor, Armoured power cable, 1.1KV grade of following sizes on the existing M.S. Tray/ walls with saddles/PVC thread screws i/c end termination of cables with glands etc as required.					
	a) 2 core X 1.5 sqmm	45	Mtrs		Mtr	
3	Dismantling of Existing Faulty / out of service console panel i/c dismantling spare cable complete as required at site .					
		1	Job		Job	
			Total Amount			

SPECIFICATIONS.

1. Work shall be carried out as per BSNL specifications.
2. Work shall be supervised by the Engineer-in-Charge.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 7 days from the date of issue of this work order.
5. The rate should be quoted inclusive of all taxes i/c GST

CONTRACTOR

**Executive Engineer (E)
BSNL Electrical Division
Dharamshala (HP)**