

**BHARAT SANCHAR NIGAM LIMITED**

**भारत संचार निगम लिमिटेड**

(A Govt. of India Enterprise)  
(भारत सरकार का उपक्रम)

**O/o Sub Divisional Engineer (E). BSNL Electrical Sub Division, 1<sup>st</sup> Floor Block No. 35 Kasumpati Shimla-171009**

कार्यालय उप मंडल अभियंता ( विद्युत ) भारत संचार निगम लिमिटेड ब्लॉक न. ३५ शिमला

No:-314/SDE/E/BSNL/ESD./SML/2020-21/40

Dated: - 25.08.2020

**Notice Inviting Quotation**

The Sub Divisional Engineer (Elect.), BSNL Electrical Sub Division, 1<sup>st</sup> Floor Block No.35 Kasumpti Shimla-171009 invites the sealed quotation for the work name mentioned below. The quotations must reach on **dt-29.08.2020** upto 15.00 Hrs.at this office & will be opened on the same day at 15.30 Hrs. The nature of job and quantum of work has been explained in the schedule given below.

**NAME OF WORK: - Replacement of faulty life expired Pumping Sets for Staff Quarters at CTO Shimla.**

S. No.	Description of items	Qty	Rate	Unit	Amount
<b>SCHEDULE OF QUANTITIES ATTACHED AS ANNEXURE-I</b>					

Note:-

1. The work shall be done as per the specification of department.
2. The work shall be supervised by the qualified Engineer-in-charge or his duly authorized representative at the site of work.
3. The layout of the work will be given by the Engineer-in-charge or his duly authorized representative at the site of work.
4. Any damage done to the building by the contractor during the execution of work shall be made good by the contractor at his risk and cost. If the damage are not made good by the contractor in reasonable time determine by the Engineer-in-charge the same will be got done at his cost departmentally after serving notice to him.
5. No extra payment will be made for any kind of transportation.
6. **The rates quoted should be inclusive of all taxes & duties but excluding GST which will be paid extra.**
7. Time allowed for completion of work shall be **15 Days**.

--Sd----

Sub Divisional Engineer (Elect.)  
BSNL Electrical Sub Division  
Shimla

From

M/s.....

Contractor Signature with Seal

ANNEXURE- I

Name of Work: - Replacement of faulty life expired Pumping Sets for Staff Quarters at CTO Shimla.

S.No.	Description	Quantity	Rate	Unit	Amount
1	Replacement of faulty/ life expired pump with new 3HP rating monoblock pumping set on common base with 2pole 3000rpm(synchronous speed max) totally enclosed fan cooled squirrel cage induction motor suitable for operation on 415 volts 3phase 50Hz 3phase a/c supply capable of discharging about 10000 ltr per Hr. against the head of 21Mts and suitable for (50x40)mm size suction and discharge line connection i/c providing suitable arrangement for priming of pump installation the same of existing cement concrete foundation testing commissioning etc as reqd at site (Make: Kirloskar, Crompton Greaves or SS Make)	1 No.		Each	
2	Replacement of faulty/ life expired pump with new 1.5HP rating self priming monoblock pumping set suitable for operation on 240 volts 1-phase 50Hz a/c supply capable of discharging about 5000 ltr per Hr. against the head of 21Mts and suitable for (25x25)mm size suction and discharge line connection complete with testing, commissioning all as required. (For CGMT residence) (Make: Kirloskar, Crompton Greaves or SS Make)	1 No.		Each	
3	SITC of 3 Phase DOL starter suitable for 3 HP motor and having 12 amp rating contactor and over load relay with range 4.0 to 6.0 A i/c fixing the same on wall and making interconnection, testing etc as reqd. (Make: Havells or SS make)	1 No.		Each	
4	Supplying and fixing 63 Amp FP MCB in the existing MCBDB i/c making connection etc as required. (L&T or SS make)	1 No.		Each	
5	Supplying and fixing 32 Amp DP MCB in 2-pole sheet steel MCB enclosure i/c making connection etc as required. (L&T or SS make)	1 No.		Each	
			Total	Rs.	

Sub Divisional Engineer (Elect.)  
BSNL Electrical Sub Division  
Shimla