



No. 7(1)/EE/E/BSNL/ED/SNR/2022-23/24

Dated : 08.06.2022

Notice Inviting Quotation

On the behalf of BSNL Tower Corporation Limited (BTCL) Subsidiary of BHARAT SANCHAR NIGAM LIMITED & The Govt. of Himachal Pradesh, The Executive Engineer (E), BSNL Electrical Division, CTTC Complex (1st Floor), Sunder Nagar (HP) pin 175002 invites the sealed quotation for following work. The quotations must reach on 14.06.2022 up 15.00 Hrs. at this office & will be opened on the same day at 15.30 Hrs. The nature of job and quantum of work has been explained in the schedule given below. The quotations can be downloaded from www.hp.bsnl.co.in

NAME OF WORK:- Special Repair & maintenance of dental OPD & (108 EMERGENCY) Hospital building at Old PHC compound at Bhunter, Distt Kullu (HP) for setting up rehabilitation center (de-addiction)[SH:- Re-arrangement of Electrical Installation]

S. No.	Description of items	Qty	Rate	Unit	Amount
	SUB HEAD-I (Wiring)				
1	Supplying and fixing of following sizes of PVC Casing Capping along with accessories on surface as required.				
1.01	20 mm X 10 mm	5 Meters		Meter	
1.02	25 mm X 15 mm	15 Meters		Meter	
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit / Casing Capping as required.				
2.01	3 X 1.5 sq. mm	10 Meters		Meter	
2.02	5 X 1.5 sq. mm	15 Meters		Meter	
2.03	9x1.5 sqmm	1 Meter		Meter	
2.04	3 x 4 sq. mm	10 Meters		Meter	
2.05	6 x 4 sq. mm	5 Meters		Meter	
3	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A piano type switch, connections, painting etc. as required.	4 Nos.		Each	
4	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 A socket outlet and 15/16 A piano type switch, connections, painting etc. as required.	8 Nos.		Each	
5	Supplying and fixing following piano type switch/socket on the existing switch box / cover including connections etc. as required.				
5.01	5/6 amps switch	21 Nos.		Each	
5.02	3 pin 5/6 A socket outlet	4 Nos.		Each	
5.03	Stepped type electronic fan regulator	4 Nos.		Each	
6	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.				
6.01	180 mm X 100 mm X 60 mm deep	3 Nos.		Each	
6.02	200 mm X 125 mm X 60 mm deep	1 No.		Each	
	TOTAL for SH-I				

	SUB HEAD-II (Fan & Fittings)				
1	SITC of following type prewired surface / recess mounted LED light fixture alongwith electronic driver including connection with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable and earthing etc. as required. (Preferred makes SYSKA/Philips/Wipro/Havells/ Crompton/Bajaj)				
1.01	20 Watt (4') SURFACE WALL Type LED light Fixture (Havells-LUMILINEBS20WLED865SPCWH, OR SS make)	7 Nos.		Each	
1.02	6.5 Watt Bulk head fittings (Havells, Model-LHEX CGP7IN5W006 OR SS make)	3 Nos.		Each	
1.03	15 Watt LED Lamp (Make- Havells)	5 Nos.		Each	
2	SITC of 1200 mm sweep ceiling fan including wiring the down rod of standard length (upto 30 cm) with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet cover on the fan box etc. as required. (M/s HAVELLS-SAM MET or similar superior make, Other preferred makes Crompton Greaves/Usha /Khaitan /Bajaj/ Orient)	4 Nos.		Each	
	TOTAL for SH-II				
	SUB HEAD-III (Distribution Boards & MCBs etc)				
1	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
1.01	16 way, Double door	1 No.		Each	
2	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
2.01	5 amps to 32 amps, 240 volts Single Pole.	14 Nos.		Each	
2.02	5 amps to 32 amps, 240 volts Double pole.	1 No.		Each	
	TOTAL for SH-III				
	G. Total of SH-I to III				
TOTAL IN WORDS : -					

TERMS / CONDITIONS

- The work shall be done as per the specification of department.
- Time allowed for completion of work shall be 07 Days from the date of issue of work order.
- The rates offered by the firm shall be Exclusive of the GST. The firm shall claim GST with the bill clearly furnishing the complete details of GST so included. BSNL, under no circumstances, will consider any claim of GST not included in the bill. It will be the firm's responsibility to settle GST with GST authorities.
- The agency will provide the workers with necessary Tools & Plant, Testing and safety equipments.
- The work shall be supervised by the qualified Engineer-in-charge or his duly authorized Representative, at the site of work.
- The layout of the work will be given by the Engineer-in-charge or his duly authorized representative at the site of work.
- Any damage done to the building by the contractor during the execution of work shall be made good by the contractor at his risk and cost, if the damage are not made good by the contractor in reasonable time determine by the Engineer-in-charge the same will be got done at his cost departmentally after serving notice to him.
- No extra payment will be made for any kind of transportation.

(----- Sd ----)
Executive Engineer (Electrical)
BSNL Electrical Division
CTTC Complex Sundernagar.

From : -

M/s.....

Contractor Signature with Seal

01/EE/E/BSNL/ED/SNR/NIQ/2022-23, dated 08.06.2022